

ROAD TRAFFIC ACT  
(CHAPTER 276, SECTIONS 119 AND 140)

ROAD TRAFFIC (TRAFFIC SIGNS) RULES

ARRANGEMENT OF RULES

Rule

1. Citation
  - 1A. Definitions
  2. Prescribed traffic signs
  3. Types of traffic signs
  4. Inscriptions on signs
  5. Change of directions
  6. Parking places
  7. Lines, markings or traffic devices on roads
  8. Bus lanes
  - 8A. Bicycle Lane
  9. Road divider
  10. Light signals for vehicles
  11. The 3-colour system
  12. The 2-colour system
  13. Light signals for lanes
  14. Miniature light signals
  15. Light signals for cyclists, pedestrians and PMD riders
  16. Light signals for bicycles, etc.
  17. Temporary beacons
  18. Temporary signs for road works
- The Schedule
- 

[1st November 1991]

**Citation**

1. These Rules may be cited as the Road Traffic (Traffic Signs) Rules.

## Definitions

1A. In these Rules, unless the context otherwise requires —

“bicycle” has the meaning given by the Act, and includes a vehicle that has 3 wheels, has pedals, and is built to be propelled solely by human power and to transport people only (with or without carry-on baggage);

“cyclist” means an individual who is riding a bicycle or power-assisted bicycle, but excludes an individual who is walking beside and pushing a bicycle or power-assisted bicycle;

“mobility scooter” and “wheeled toy” have the meanings given by section 2(1) of the Active Mobility Act 2017 (Act 3 of 2017);

“pedestrian” means —

- (a) an individual walking, with or without animals;
- (b) an individual in a non-motorised wheelchair;
- (c) an individual driving a motorised wheelchair or riding a mobility scooter;
- (d) an individual travelling on inline skates, roller-skates or a wheeled toy;
- (e) an individual pushing a pram, stroller or trolley, or a motorised or non-motorised wheelchair; or
- (f) an individual walking beside and pushing a bicycle, power-assisted bicycle, personal mobility device or any other vehicle;

“PMD” means a personal mobility device;

“PMD rider” means an individual who is riding a personal mobility device on a road as permitted by section 5A(2) of the Act, but excludes an individual who is walking beside and pushing a PMD.

[S 276/2018 wef 05/05/2018]

### **Prescribed traffic signs**

2.—(1) Subject to any directions which the Minister may give under section 119 of the Act, the traffic signs authorised to be drawn or placed on or near any road shall —

- (a) be at least of the size, and conform to the colour and type as prescribed in the diagrams set out in the Schedule; and
- (b) conform to the descriptions set out in these Rules.

(2) The dimension of the traffic signs as given in the diagrams set out in the Schedule denotes the dimension in millimetres unless otherwise stated.

(3) A traffic sign drawn or placed on or near a road shall be deemed to be a prescribed traffic sign and to have been so lawfully drawn or placed unless the contrary is proved.

(4) The fact that a traffic sign differs slightly in size, colour or type from that prescribed in these Rules shall not prevent the traffic sign from being a regular or lawful sign so long as the sign is not thereby misleading or its general appearance materially altered or its effectiveness impaired.

### **Types of traffic signs**

3. The traffic signs set out in the Schedule are divided as follows:

- (a) regulatory signs as set out in Part I of the Schedule which are intended to inform road users of special obligations, restrictions and prohibitions with which they must comply and are subdivided into —
  - (i) mandatory signs;
  - (ii) priority signs; and
  - (iii) prohibitory or restrictive signs;
- (b) warning signs as set out in Part II of the Schedule which are intended to warn road users of the danger on the road and to inform them of the nature and source of the danger; and

- (c) informative signs as set out in Part III of the Schedule which are intended to provide road users with information which may be useful while they are travelling.

### **Inscriptions on signs**

4. The inscription on the traffic signs shall be in the English language except that there may also be inscription in another language or languages on the signs.

### **Change of directions**

5. The direction of any arrow or other indication on the signs shown in the diagrams in the Schedule may be reversed or otherwise varied as circumstances may require.

### **Parking places**

6. The signs shown in diagrams 36(a) to 36(f) in Part I of the Schedule shall be used only in connection with parking places owned by or under the control of the Government or statutory bodies.

### **Lines, markings or traffic devices on roads**

7.—(1) Lines, markings and other traffic devices may be drawn or placed on a road to indicate —

- (a) the position where vehicles shall stop or reduce speed when required to do so by a traffic sign, or a police officer engaged in the control of traffic;
- (b) the course and direction to be followed by traffic;
- (c) a street refuge;
- (d) places reserved for bus terminals, bus stops, taxi stands, taxi stops, trishaw stands, motor cycle parks, bicycle parks, car parks, coach parks, lorry parks, trailer parks, loading and unloading bays and vehicles of handicapped persons;
- (e) a pedestrian crossing;
- (f) a bicycle crossing;
- (g) the edge of the road;

(h) a central reservation which divides the road for the safety or guidance of traffic;

(i) a yellow box;

(j) a road shoulder along an expressway;

(ja) a bicycle lane;

*[S 172/2017 wef 22/04/2017]*

(k) a part-day bus lane;

*[S 639/2005 wef 03/10/2005]*

(ka) a full-day bus lane;

*[S 639/2005 wef 03/10/2005]*

(l) the section of the road where parking of vehicles is restricted or prohibited;

(m) the boundary on the road which no vehicle, whether overtaking other vehicles or not, shall cross;

*[S 651/2008 wef 20/12/2008]*

(n) a parking place or a public service vehicle stand;

*[S 651/2008 wef 20/12/2008]*

(o) a Bus Give-Way Controlled Area;

*[S 651/2008 wef 20/12/2008]*

(p) a Bus Give-Way Line; and

*[S 651/2008 wef 20/12/2008]*

(q) a Bus Give-Way Box.

*[S 651/2008 wef 20/12/2008]*

(2) The lines, markings and other traffic devices drawn or placed on a road shall be painted or indicated by other suitable material in white, yellow or red.

(3) The width of longitudinal lines on a road shall not be less than 100 mm and the width of transverse lines on a road shall not be less than 200 mm.

(4) A zebra pedestrian crossing is indicated by markings across a road as shown in diagram 142(a), 142(b), 143(a), 143(b), 144(a) or

144(b) in Part III of the Schedule and such crossing may, in addition, also be identified on either side of the road by a pair of —

- (a) traffic signs facing approaching vehicles as set out in diagram 125(a) in Part III of the Schedule; or
- (b) amber beacons of not less than 300 mm in diameter which may be intermittently or otherwise internally illuminated.

(5) A signalised pedestrian crossing is indicated by 2 parallel, continuous or broken white lines each of not less than 200 mm in width and spaced not less than 3,000 mm apart from each other, and with the 2 lines running from one edge of the road to the other as shown in diagrams 140(a), 140(e) and 145 in Part III of the Schedule.

*[S 158/2018 wef 01/04/2018]*

(6) A pedestrian crossing (other than a signalised pedestrian crossing) at a signal-controlled junction is indicated by 2 parallel yellow lines each of not less than 300 mm in width and spaced not less than 3,000 mm apart from the centre to centre from one edge of the road to the other as shown in diagram 140(e) in Part III of the Schedule.

(7) A signalised bicycle crossing is indicated by 2 parallel white lines each of not less than 300 mm in width and spaced not less than 3,000 mm apart from the centre of one line to the other and with the 2 lines running from one edge of the road, subway or bridge, as the case may be, to the other as shown in diagram 145(a) in Part III of the Schedule.

(8) A yellow box is indicated by yellow lines connecting the 4 corners of an area of road at a road junction or on any part of the road as shown in diagrams 140(a) to 140(d) in Part III of the Schedule.

(9) A road shoulder is the strip constructed with a surface suitable for motor vehicles to move along or stop, along the left (nearside) or right (offside) of a road and is demarcated from the road by a continuous white marginal line of not less than 300 mm in width as shown in diagram 151(e) in Part III of the Schedule.

(10) The edge of a road is indicated by a continuous or broken white marginal line of not less than 300 mm in width as shown in diagrams 139(b) and 139(c) in Part III of the Schedule.

(11) A part-day bus lane is the section of a road marked by a longitudinal continuous yellow line of not less than 300 mm in width and transverse yellow lines of not less than 200 mm in width and 1,200 mm in length as shown in diagrams 115(a) to 115(d) in Part III of the Schedule.

*[S 639/2005 wef 03/10/2005]*

(11A) A full-day bus lane is the section of a road marked by —

(a) a longitudinal continuous yellow line of not less than 300 mm in width parallel to a longitudinal continuous red line of not less than 150 mm in width; and

(b) transverse yellow lines of not less than 200 mm in width and 1,200 mm in length,

as shown in diagrams 115(e) to 115(h) in Part III of the Schedule.

*[S 639/2005 wef 03/10/2005]*

(11B) A bicycle lane is the section of a road, marked by —

(a) a longitudinal, continuous chevron marking; and

(b) a bicycle symbol that appears at regular intervals on that section of the road.

*[S 172/2017 wef 22/04/2017]*

(11C) The markings mentioned in paragraph (11B) are shown in diagram 166 in Part III of the Schedule.

*[S 172/2017 wef 22/04/2017]*

(12) The boundary which no vehicle shall cross under paragraph (1)(m) is indicated by continuous double white lines as shown in diagram 150(a) in Part III of the Schedule.

(13) A parking place or a public service vehicle stand is indicated by broken or continuous lines as shown in diagram 156 in Part III of the Schedule.

(14) A Bus Give-Way Controlled Area is the section of a road marked by white triangle markings and the word “Bus” in white as shown in diagram 116(d) in Part III of the Schedule.

*[S 651/2008 wef 20/12/2008]*

(15) A Bus Give-Way Box is the section of a road painted in yellow and marked by an arrow, which —

- (a) appears after a Bus Give-Way Controlled Area; and
- (b) is separated from the Bus Give-Way Controlled Area by a Bus Give-Way Line,

as shown in diagram 116(d) in Part III of the Schedule.

*[S 651/2008 wef 20/12/2008]*

### **Bus lanes**

**8.—**(1) Except on any Saturday, Sunday or public holiday, no person shall drive a vehicle other than an omnibus, or cause or permit any such vehicle to remain, on a part-day bus lane during the hours of 7.30 a.m. to 9.30 a.m. and 5 p.m. to 8 p.m.

*[S 134/2007 wef 01/04/2007]*

(1A) Except on any Sunday or public holiday, no person shall drive a vehicle other than an omnibus, or cause or permit any such vehicle to remain, on a full-day bus lane during the hours of 7.30 a.m. to 11 p.m.

*[S 134/2007 wef 01/04/2007]*

*[S 114/2016 wef 21/03/2016]*

(2) Paragraphs (1) and (1A) shall not apply to —

- (a) the driver of an ambulance, fire engine or any vehicle for police or rescue purposes on urgent duty call if the approach of such vehicle is made known by means of some distinctive siren, bell or multi-toned horn, as the case may be;
- (b) a cyclist who is not cycling alongside of another bicycle or power-assisted bicycle on his left;

*[S 276/2018 wef 05/05/2018]*

- (c) the driver of a motor vehicle who drives along the bus lane in order to avoid causing danger to any person or a collision with any other vehicle if that driver does not

cause or permit the vehicle to remain on the bus lane longer than is necessary to avoid causing such danger or collision;

*[S 549/2001 wef 01/11/2001]*

(d) the driver of a school bus, a private hire bus or an excursion bus when it is used to carry passengers for reward under a Supplementary Public Transport Scheme in accordance with —

(i) a public service vehicle licence that is issued for that bus under section 102 of the Act; and

(ii) a bus service licence that is granted or is deemed granted under section 13 of the Bus Services Industry Act 2015 (Act 30 of 2015); and

*[S 676/2016 wef 01/01/2017]*

(e) the driver of any other bus except that he shall not stop the bus in a bus lane or at a bus stand or bus bay within a bus lane for any purpose other than for the purpose of negotiating traffic.

*[S 549/2001 wef 01/11/2001]*

*[S 114/2016 wef 21/03/2016]*

(3) In this rule, “bus lane” means any full-day or part-day bus lane.

*[S 639/2005 wef 03/10/2005]*

## **Bicycle Lane**

**8A.** A person must not park a vehicle on a bicycle lane at any time.

*[S 172/2017 wef 22/04/2017]*

## **Road divider**

**9.** No vehicle shall pass over a road divider.

## **Light signals for vehicles**

**10.** Vehicular traffic may be regulated by the following light signals:

(a) a 3-colour system;

(b) a 2-colour system;

- (c) lane use light signals; and
- (d) restricted zone light signals.

### The 3-colour system

#### 11. In a 3-colour system —

- (a) the signals shall consist of 3 lights, which shall be red, amber and green respectively, except that there may be —
  - (i) any red, amber or green arrow light;
  - (ii) any combination of red, amber or green arrow lights;  
or
  - (iii) such other additional green light or lights as may be provided for in this rule for special purposes;
- (b) the signals shall consist of 3 arrows (either in left, right or straight ahead direction), which shall be red, amber and green respectively, except that there may be —
  - (i) any red, amber or green arrow light;
  - (ii) any combination of red, amber or green arrow lights;  
or
  - (iii) such other additional green light or lights as may be provided for in this rule for special purposes;
- (c) the red, amber and green lights shall be arranged vertically or horizontally facing the direction of approaching traffic and —
  - (i) where they are arranged vertically, the red light shall be placed above the amber light and the green light shall be placed below the amber light;
  - (ii) where they are arranged horizontally, the red light shall be placed on the right of the amber light and the green light shall be placed on the left of the amber light;
  - (iii) where they are arranged vertically with any combination of red, amber or green arrow lights,

- each arrow light shall be placed at the same level with a light of the same colour; and
- (iv) where they are arranged horizontally with any combination of red, amber or green arrow lights, each arrow light shall be placed below the light of the same colour;
- (d) any additional arrow light referred to in paragraph (a)(i) shall be placed —
- (i) at the same level of the light of the same colour where the lights are arranged vertically;
  - (ii) above the red light where the lights are arranged vertically; or
  - (iii) below the light of the same colour where the lights are arranged horizontally;
- (e) any additional green light referred to in paragraph (a)(iii) shall be placed at the same level on the left side of or above the red light facing the direction of the approaching traffic where the lights are arranged vertically;
- (f) the red, amber and green arrow lights of the same direction shall be arranged vertically or horizontally facing the direction of approaching traffic and —
- (i) where they are arranged vertically, the red arrow light shall be placed above the amber arrow light and the green arrow light shall be placed below the amber arrow light;
  - (ii) where they are arranged horizontally, the red arrow light shall be placed on the right of the amber arrow light and the green arrow light shall be placed on the left of the amber arrow light;
  - (iii) where they are arranged vertically with any combination of red, amber and green arrow lights of different directions, they shall be placed at the same level of the arrow lights of the same colour; and

- (iv) where they are arranged horizontally with any combination of red, amber and green arrow lights of different directions, they shall be placed below the arrow light of the same colour;
- (g) any additional arrow light referred to in paragraph (b) (i) shall be placed —
  - (i) at the same level of the arrow light of the same colour where the arrow lights are arranged vertically;
  - (ii) above the red arrow light where the arrow lights are arranged vertically; and
  - (iii) below the arrow light of the same colour where the arrow lights are arranged horizontally;
- (h) any additional green light referred to in paragraph (b) (iii) shall be placed at the same level on the left side of or above the red arrow light facing the direction of the approaching traffic where the lights are arranged vertically;
- (i) where the lights and arrow lights are arranged vertically —
  - (i) the effective diameter of the lens of each light and arrow light shall be at least 200 mm;
  - (ii) the height of the centre of the lens of the light or arrow light nearest to the ground surface shall be 2,290 mm except that it may be increased to 3,000 mm where owing to road gradient it is desirable to do so; and
  - (iii) the centres of the lenses of the 2 lights, 2 arrow lights or any combination thereof placed next to each other shall not be more than 500 mm apart;
- (j) where the lights and arrow lights are arranged horizontally —
  - (i) the effective diameter of the lens of each light and arrow light shall be at least 300 mm;

- (ii) the height of the centre of the lens of the light or arrow light nearest to the ground surface shall not be less than 5,200 mm; and
  - (iii) the centres of the lenses of the 2 lights, 2 arrow lights or any combination thereof placed next to each other shall not be more than 500 mm apart; and
- (k) subject to the directions of any police officer who may be engaged in the control of traffic —
- (i) the illuminated red light shall be taken as prohibiting vehicles from proceeding beyond the stop line or broken lines on the road provided in conjunction with the signals, subject to sub-paragraphs (v), (ix), (x) and (xi);
  - (ii) the illuminated amber light shall be taken to denote an impending change from green light to red light and as prohibiting vehicles from proceeding beyond the stop line or broken lines on the road provided in conjunction with the signals except in the case of any vehicle which is so close to such line when the amber light first appears that it cannot safely be stopped before the line;
  - (iii) the illuminated green light shall be taken to indicate that vehicles may pass the signal and proceed straight on, or with due regard to the safety of other users of the road and precedence to pedestrians and on-coming traffic, turn left or right subject to any sign prohibiting left or right turn or in conjunction with the arrow light signals, subject to sub-paragraphs (x) and (xi);
  - (iv) where the green light shows one or more illuminated arrow or arrows, it shall be taken to indicate that vehicles may only proceed in the direction or directions indicated by the arrow or arrows (where the arrow points upwards, vehicles may only proceed straight ahead);

- (v) where the signals consist of one or more additional green arrow light or lights —
    - (A) the illuminated green arrow light or lights shall be taken to indicate that vehicles, notwithstanding that they would otherwise be required by the illuminated red or amber light to stop, may proceed in the direction or directions indicated by the green arrow or arrows with precedence to pedestrians; and
    - (B) the illuminated intermittent green arrow flashing light shall be taken as prohibiting vehicles from proceeding beyond the stop line on the road provided in conjunction with the signals except in the case of any vehicle which is so close to such line when the green arrow light first flashes that it cannot safely be stopped before the line;
  - (vi) where the signals consist of an additional green light showing the letter “B”, it shall be taken to indicate that any bus in the innermost left lane of the road before the stop line or broken lines on the road provided in conjunction with the signals may —
    - (A) notwithstanding that it would otherwise be required by the illuminated red light to stop; and
    - (B) if its path is not obstructed by another vehicle, pass the signal and proceed straight on;
- [S 549/2001 wef 01/11/2001]*
- (vii) the illuminated intermittent red light and the illuminated intermittent red arrow light flashing at the rate of between 60 to 80 flashes per minute shall be taken to indicate that vehicles shall stop at the stop line provided in conjunction with the signals and may thereafter, with caution and due regard to the safety of other users of the road and precedence to

pedestrians and to traffic in other directions, proceed beyond the stop line;

(viii) the illuminated intermittent amber light and the illuminated intermittent amber arrow light flashing at the rate of between 60 to 80 flashes per minute shall be taken to indicate that vehicles shall slow down on approaching the signals and may thereafter, with caution and due regard to the safety of other users of the road and precedence to pedestrians, proceed beyond the stop line provided in conjunction with the signals;

(ix) where allowed by the appropriate sign as shown in diagram 161 (a) or 161 (b) in Part III of the Schedule, a vehicle which —

(A) is on a lane from which a left turn or a right turn may, by virtue of any sign or marking as shown in the Schedule, be made; and

(B) in compliance with the illuminated red light, has stopped at the stop line or broken lines on the road provided in conjunction with the signals,

may, with caution and due regard to the safety of other users of the road and precedence to pedestrians and to traffic in other directions, proceed beyond the stop line or broken lines and make a left turn or a right turn, as the case may be;

(x) the illuminated red arrow light shall be taken as prohibiting vehicles from proceeding beyond the stop line or broken lines on the road in that direction, notwithstanding sub-paragraphs (vi) and (ix);

(xi) the illuminated amber arrow light shall be taken to denote an impending change from green arrow light to red arrow light and as prohibiting vehicles from proceeding beyond the stop line or broken lines on the road provided in conjunction with the signals

except in the case of any vehicle which is so close to such line when the amber arrow light first appears that it cannot safely be stopped before the line, notwithstanding that they would otherwise be required by the illuminated green or amber light or lights to proceed on; and

- (xii) the illuminated green arrow light shall be taken to indicate that vehicles, notwithstanding that they would otherwise be required by the illuminated red or amber lights to stop, may proceed in the direction or directions indicated by the green arrow or arrows with precedence to pedestrians.

*[S 13/2000 wef 14/01/2000]*

### **The 2-colour system**

**12.**—(1) In a 2-colour system —

- (a) the signals shall consist of a red and green light; and
- (b) the red light and the green light shall not be illuminated simultaneously.

(2) The 2-colour system shall only be used in temporary installations.

### **Light signals for lanes**

**13.** In the case of light signals regulating the use of traffic lanes —

- (a) the signals shall consist of 3 lights, which shall be a green downward arrow light, an amber inclined crossed bars light and a red inclined crossed bars light respectively and arranged horizontally facing the direction of approaching traffic;
- (b) the effective diameter of the lens of each light shall be at least 300 mm;
- (c) the height of the centre of the lens of each light above the road shall not be less than 5,200 mm;

- (d) the centres of the lenses of 2 lights placed next to each other shall not be more than 400 mm apart;
- (e) the illuminated green light shall be taken to indicate that vehicles may proceed along the lane over which the light is placed;
- (f) the illuminated intermittent amber flashing light shall be taken to indicate that vehicles may proceed with caution along the lane over which the light is placed; and
- (g) the illuminated red light shall be taken to indicate that vehicles shall not proceed beyond the signal light along the lane over which the light is placed.

### **Miniature light signals**

**14.** The 3-colour system light signals may be supplemented with miniature light signals which shall be the same as the 3-colour system light signals where the red, amber and green lights are arranged vertically except that —

- (a) the effective diameter of the lens of each light shall be at least 100 mm;
- (b) the height of the centre of the lens of the green light above the road shall be at least 1,200 mm; and
- (c) the centres of the lenses of 2 lights placed next to each other shall not be more than 150 mm apart.

### **Light signals for cyclists, pedestrians and PMD riders**

**15.—(1)** Light signals may be used to indicate to pedestrians, PMD riders and cyclists the period during which they should or should not cross the road.

*[S 276/2018 wef 05/05/2018]*

(2) The light signals for pedestrians, PMD riders and cyclists shall consist of one red light with the figure of a red man standing upright and one green light with the figure of a green man walking.

*[S 276/2018 wef 05/05/2018]*

(3) The effective diameter of the lens of each light shall not be less than 300 mm.

(4) The height of the centre of the lens of the green light above the road shall be 2,290 mm except that it may be increased where owing to road gradient it is desirable to do so.

(5) The centre of the lenses of the lights shall not be more than 350 mm apart.

(6) The post on which the lights are supported may be painted black and yellow in alternate horizontal bands.

(7) The illuminated red man light shall be taken to indicate that the pedestrian, PMD rider or cyclist shall not cross the road.

*[S 276/2018 wef 05/05/2018]*

(8) The illuminated green man light shall be taken to indicate that the pedestrian, PMD rider or cyclist may cross the road.

*[S 276/2018 wef 05/05/2018]*

(9) The flashing green man light shall be taken to indicate that the red man light is about to be illuminated.

*[S 276/2018 wef 05/05/2018]*

### **Light signals for bicycles, etc.**

**16.—**(1) Light signals may be used to indicate to cyclists, PMD riders and pedestrians the period during which they should or should not cross the road, subway or bridge, as the case may be.

*[S 276/2018 wef 05/05/2018]*

(2) The light signals for cyclists, PMD riders and pedestrians shall consist of one red light with the picture of a red bicycle and one green light with the picture of a green bicycle.

*[S 276/2018 wef 05/05/2018]*

(3) The effective diameter of the lens of each light shall not be less than 300 mm.

(4) The height of the centre of the lens of the green light above the surface of the road, including that in a subway or on a bridge, as the case may be, shall be 2,290 mm except that it may be increased where owing to the gradient of the surface it is desirable to do so.

(5) The centre of the lens of the lights shall not be more than 350 mm apart.

(6) The post on which the lights are supported may be painted black and yellow in alternate horizontal bands.

(7) The illuminated red bicycle light shall be taken to indicate that the cyclist, PMD rider or pedestrian shall not cross the road.

*[S 276/2018 wef 05/05/2018]*

(8) The illuminated green bicycle light shall be taken to indicate that the cyclist, PMD rider or pedestrian may cross the road.

*[S 276/2018 wef 05/05/2018]*

(9) The flashing green bicycle light shall be taken to indicate that the red bicycle light is about to be illuminated.

*[S 276/2018 wef 05/05/2018]*

### **Temporary beacons**

**17.**—(1) Temporary beacons showing an intermittent amber flashing light may be used on special occasions or in connection with road works to assist the safe movement of traffic.

(2) The temporary beacons shall conform to the following provisions:

- (a) the effective diameter of the lenses shall not be less than 125 mm nor more than 200 mm;
- (b) the height of the centre of the lens above the road shall not be less than 1,000 mm nor more than 1,200 mm;
- (c) the rate of flashing shall be between 60 to 80 flashes per minute; and
- (d) the beacons shall be mounted on a beam or a traffic cone or posted on to a barricade.

### **Temporary signs for road works**

**18.**—(1) Where road works are in progress or where for some other reason the width of the road is temporarily reduced, the traffic signs in diagrams 7 and 8 in Part I of the Schedule may be used to control traffic.


(2) Nothing in this rule shall prevent the use for the purpose stated in paragraph (1) of devices which on 15th November 1991 are already in the possession of the Government, any statutory body which has the lawful authority to break up a road, or the contractors engaged in the business of marking and repairing roads.

THE SCHEDULE

PART I

MANDATORY SIGNS

DIAGRAM 1



AHEAD ONLY


This sign indicates that vehicles shall only proceed in the direction of the arrow. It may be further qualified when used with supplementary plates.



THE SCHEDULE — *continued*

The direction of the arrow may be reversed to indicate —  
KEEP RIGHT

This sign indicates that vehicles shall keep left (or right). It may be further qualified when used with supplementary plates.




TURN LEFT AHEAD

The direction of the arrow may be reversed to indicate —  
TURN RIGHT AHEAD

This sign indicates that vehicles shall only turn in the direction of the arrow at the junction ahead. It may be further qualified when used with supplementary plates.

THE SCHEDULE — continued


DIAGRAM 5



PASS EITHER SIDE

This sign indicates that vehicles shall pass on either side of the sign.

DIAGRAM 6




THE SCHEDULE — *continued*

STOP CHILDREN

This sign indicates that vehicles shall not proceed beyond the sign.


DIAGRAM 7



This sign indicates that vehicles may proceed beyond the sign.

THE SCHEDULE — continued

DIAGRAM 8




This sign indicates that vehicles shall not proceed beyond the sign.

PRIORITY SIGNS

THE SCHEDULE — continued

DIAGRAM 9




STOP

This sign indicates that vehicles shall, before entering the junction ahead, stop at the transverse stop line drawn in conjunction with the sign.



THE SCHEDULE — *continued*


DIAGRAM 10A



This sign indicates that vehicles shall stop before the Bus Give-Way Line and give precedence to any bus entering or waiting to enter the Bus Give-Way Box.

DIAGRAM 10B

THE SCHEDULE — *continued*



CARS AND MOTOR CYCLES ONLY LANE

This sign indicates that only cars and motor cycles may be used on such lanes found directly below this sign.

DIAGRAM 10C



ALL VEHICLES LANE

This sign indicates that any class of vehicles may be used on such lanes found directly below this sign. This sign serves as a supplement to diagram 10B and indicates that the lanes found directly below this sign are not subject to the prohibition or restriction in diagram 10B.


[S 189/2017 wef 28/04/2017]

[S 651/2008 wef 20/12/2008]

THE SCHEDULE — *continued*

PROHIBITORY AND RESTRICTIVE SIGNS

DIAGRAM 11




NO ENTRY

This sign prohibits the entry of all vehicles unless otherwise indicated by a supplementary plate.

THE SCHEDULE — continued

DIAGRAM 12




MAXIMUM SPEED LIMIT

This sign indicates that vehicles shall not travel at more than the speed of 50 km per hour. The numerals on the sign may be altered to indicate different speed limit.

THE SCHEDULE — *continued*

**DIAGRAM 12A**




**SCHOOL ZONE, 40 KM/H WHEN LIGHTS FLASH**

This sign is placed at the start of a demarcated school zone. It indicates that the section of road ahead fronts a school and that vehicles shall not travel at more than 40 km per hour in the school zone when the accompanying amber lights are flashing alternately.

[S 670/2014 wef 01/10/2014]

THE SCHEDULE — *continued*

DIAGRAM 12B




SILVER ZONE, 40 KM/H

This sign is placed at the start of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road ahead and that vehicles must not travel at more than 40 km per hour in the silver zone.

[S 95/2020 wef 01/03/2020]

THE SCHEDULE — continued

DIAGRAM 12C



SILVER ZONE, 30 KM/H

This sign is placed at the start of a demarcated silver zone. It indicates that


THE SCHEDULE — continued

elderly pedestrians are likely to be encountered in the section of road ahead and that vehicles must not travel at more than 30 km per hour in the silver zone.

[S 95/2020 wef 01/03/2020]

[S 670/2014 wef 01/10/2014]

DIAGRAM 13




WIDTH LIMIT

This sign prohibits the entry of vehicles with width in excess of 2.3 metres. The numerals on the sign may be altered to indicate different width restriction.

THE SCHEDULE — *continued*

DIAGRAM 14




WEIGHT LIMIT

This sign prohibits the entry of vehicles with weight laden or unladen in excess of 10 tonnes. The numerals on the sign may be altered to indicate different weight restriction.

THE SCHEDULE — *continued*

DIAGRAM 15




HEIGHT LIMIT

This sign prohibits the entry of vehicles with an overall height in excess of 4.5 metres. The numerals on the sign may be altered to indicate different height restriction.

THE SCHEDULE — *continued*

DIAGRAM 16




NO WAITING

This sign prohibits the waiting of vehicles. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

THE SCHEDULE — *continued*

DIAGRAM 16 (a)




NO WAITING

This sign prohibits the waiting of vehicles.

SCALE: 1:5

THE SCHEDULE — continued

DIAGRAM 16 (b)




NO WAITING

This sign prohibits the waiting of vehicles, and indicates the point where the prohibition begins.

SCALE: 1:5

THE SCHEDULE — *continued*

DIAGRAM 16 (c)




NO WAITING

This sign prohibits the waiting of vehicles, and indicates the point where the prohibition ends.

SCALE: 1:5

THE SCHEDULE — *continued*

DIAGRAM 17




NO STOPPING

This sign prohibits the stopping of vehicles unless the vehicle is prevented from proceeding due to traffic conditions. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

THE SCHEDULE — *continued*

DIAGRAM 17 (a)




NO STOPPING

This sign prohibits the stopping of vehicles unless the vehicle is prevented from proceeding due to traffic conditions.

SCALE: 1:5

THE SCHEDULE — continued

DIAGRAM 17 (b)




NO STOPPING

This sign prohibits the stopping of vehicles unless the vehicle is prevented from proceeding due to traffic conditions, and indicates the point where the prohibition begins.

SCALE: 1:5

THE SCHEDULE — *continued*

DIAGRAM 17 (c)




NO STOPPING

This sign prohibits the stopping of vehicles unless the vehicle is prevented from proceeding due to traffic conditions, and indicates the point where the prohibition ends.

SCALE: 1:5

THE SCHEDULE — continued

DIAGRAM 18




NO OVERTAKING

This sign prohibits the overtaking of motor vehicles. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

THE SCHEDULE — *continued*

DIAGRAM 19




LORRY RESTRICTION

This sign prohibits the entry of all goods vehicles. It may be further qualified when used with supplementary plates eg. “Exceeding 2,500 kg in unladen weight”.

DIAGRAM 19A

THE SCHEDULE — continued




BUS AND GOODS VEHICLES RESTRICTION

This sign prohibits the entry of all buses and goods vehicles. It may be further qualified when used with supplementary plates.

[S 189/2017 wef 28/04/2017]


THE SCHEDULE — continued



RESTRICTION OF MOVEMENT OF VEHICLES WITH 3 OR MORE AXLES

THE SCHEDULE — *continued*

DIAGRAM 20A




RESTRICTION OF MOVEMENT OF TRAILERS WITH CONTAINERS

This sign prohibits the movement of all trailers with containers on the section of the road beyond the point marked by the sign between 7.30 a.m. and 8 p.m. of any day from Monday to Friday (except public holidays). The days and times on the sign may be altered to indicate different days and times during which the prohibition applies.

[S 814/2013 wef 29/12/2013]

THE SCHEDULE — continued

DIAGRAM 21




PEDESTRIAN CROSSING PROHIBITION

This sign prohibits pedestrians, PMD riders and cyclists from crossing the road without using the designated pedestrian crossing. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

[S 276/2018 wef 05/05/2018]

DIAGRAM 22



THE SCHEDULE — *continued*

DIAGRAM 23






DIAGRAM 24



THE SCHEDULE — continued

DIAGRAM 24 (a)



MESSAGE (BLACK)  
ON REVERSED SIDE  
(WHITE):—


1. CYCLISTS  
Please Use Crossing
2. CYCLISTS  
Please Use Underpass
3. CYCLISTS  
Please Use Overpass

CYCLIST AND PMD RIDER CROSSING PROHIBITION

This sign indicates that cyclists and PMD riders shall not cross that section of the road, subway or bridge, as the case may be, without using the designated bicycle crossing. It may be used in conjunction with supplementary plates to indicate the section of that road, subway or bridge to which the prohibition applies.

[S 276/2018 wef 05/05/2018]

DIAGRAM 24 (b)



THE SCHEDULE — *continued*

DIAGRAM 24 (c)






DIAGRAM 24 (d)



CYCLIST AND PMD RIDER CROSSING PROHIBITION (MESSAGE ON REVERSED SIDE)

DIAGRAM 24(e)


THE SCHEDULE — *continued*



PEDESTRIANS, CYCLISTS AND PMD RIDERS  
CROSSING PROHIBITION SIGN

This sign prohibits pedestrians, cyclists and PMD riders from crossing the road without using the designated crossing. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

DIAGRAM 24(f)




THE SCHEDULE — *continued*

PEDESTRIANS, CYCLISTS AND PMD RIDERS  
CROSSING PROHIBITION SIGN

This sign prohibits pedestrians, cyclists and PMD riders from crossing the road without using the designated crossing. This sign may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

DIAGRAM 24(g)




PEDESTRIANS, CYCLISTS AND PMD RIDERS  
USE CROSSING SIGN

This sign indicates that pedestrians, cyclists and PMD riders are to cross the road using the designated crossing.

DIAGRAM 24(h)


THE SCHEDULE — *continued*



PEDESTRIANS, CYCLISTS AND PMD RIDERS  
USE OVERPASS SIGN

This sign indicates that pedestrians, cyclists and PMD riders are to cross the road using the designated overpass.

DIAGRAM 24(i)




THE SCHEDULE — *continued*

PEDESTRIANS, CYCLISTS AND PMD RIDERS  
USE UNDERPASS SIGN

This sign indicates that pedestrians, cyclists and PMD riders are to cross the road using the designated underpass.

[S 276/2018 wef 05/05/2018]




DIRECTIONAL ARROWS

These supplementary signs, when used in conjunction with prohibitory or restrictive signs, indicate the section of the road to which the prohibition or restriction applies.

THE SCHEDULE — continued

DIAGRAM 26




MOTOR CYCLES, POWER-ASSISTED BICYCLES AND PEDAL-CYCLES RESTRICTION

This sign prohibits the entry of motor cycles, power-assisted bicycles and pedal-cycles ie. trishaws, tricycles and bicycles.

[S 276/2018 wef 05/05/2018]

DIAGRAM 27




THE SCHEDULE — *continued*

PEDESTRIAN, POWER-ASSISTED BICYCLES AND PEDAL-CYCLES  
RESTRICTION

This sign prohibits the entry of pedestrians, power-assisted bicycles and pedal-cycles ie. trishaws, tricycles and bicycles.

[S 276/2018 wef 05/05/2018]


DIAGRAM 28



This sign prohibits the parking of motor vehicles with less than 4 wheels weighing not more than 470 kilograms.

THE SCHEDULE — continued


DIAGRAM 29



COMPULSORY CYCLE TRACK

This sign indicates that cyclists shall use the cycle track.

DIAGRAM 30



This sign prohibits the entry of bicycles and power-assisted bicycles.

[S 276/2018 wef 05/05/2018]

THE SCHEDULE — *continued*

DIAGRAM 30A



NO RIDING


This sign prohibits the riding of power-assisted bicycles and pedal-cycles, i.e. trishaws, tricycles and bicycles, beyond the point marked by the sign. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

[S 276/2018 wef 05/05/2018]

[S 577/2005 wef 05/09/2005]


THE SCHEDULE — continued

DIAGRAM 31



This sign prohibits the entry of motor cycles.

DIAGRAM 32




HAZARDOUS LOADS PROHIBITION

This sign prohibits the entry of vehicles transporting hazardous loads.

THE SCHEDULE — *continued*


DIAGRAM 33



NO RIGHT TURN

This sign prohibits vehicles from turning right at the junction ahead. It may be used in conjunction with traffic light signals and the prohibition may be qualified by a supplementary plate.

DIAGRAM 34




NO LEFT TURN

This sign prohibits vehicles from turning left at the junction ahead. It may be used in conjunction with traffic light signals and the prohibition may be qualified by a supplementary plate.

THE SCHEDULE — *continued*


DIAGRAM 35



NO HORNING

This sign prohibits honking except in an emergency.

DIAGRAM 36 (a)




This sign indicates a designated pay parking place for motor vehicles with weight unladen exceeding 1,500 kilograms.



THE SCHEDULE — *continued*


DIAGRAM 36 (d)



PARKING PLACES SIGN (URA)

This sign indicates a designated pay parking place where parking coupons are to be used.


THE SCHEDULE — continued



PARKING PLACE SIGN (HDB)


This sign indicates a designated pay parking place where parking coupons are to be used and/or where season parking is applicable.

THE SCHEDULE — continued



NO PARKING OF BUS AND LORRY


This sign prohibits the parking of buses and lorries.



THE SCHEDULE — *continued*

This marking indicates that vehicles on the lane with the marking may only proceed ahead.


DIAGRAM 38



This marking indicates that vehicles on the lane with the marking may only turn left or right.

THE SCHEDULE — *continued*

DIAGRAM 39




This marking indicates that vehicles on the lane with the marking may only proceed straight ahead or turn right.



THE SCHEDULE — *continued*

DIAGRAM 40A



NO WALKING WITHIN BUS PARK

This sign indicates that unauthorised persons are prohibited from walking within the bus park.


[S 334/2003 wef 14/07/2003]

PART II

WARNING SIGNS

THE SCHEDULE — continued


DIAGRAM 41



TWO WAY TRAFFIC

This sign indicates that the section of the road ahead carries two-way traffic.

DIAGRAM 42




TWO-WAY TRAFFIC ACROSS A ONE-WAY CARRIAGEWAY

This sign indicates that the transverse road ahead carries two-way traffic.

THE SCHEDULE — continued


DIAGRAM 43



ROAD NARROWS ON BOTH SIDES AHEAD

This sign indicates that the road ahead narrows on both sides.

DIAGRAM 44



ROAD NARROWS ON RIGHT AHEAD


This symbol may be reversed to indicate —

ROAD NARROWS ON LEFT AHEAD

This sign indicates that the road ahead narrows on the right (or left) side.

THE SCHEDULE — *continued*

DIAGRAM 45




BEND TO THE RIGHT AHEAD

This symbol may be reversed to point to the left to indicate —

BEND TO THE LEFT AHEAD

This sign indicates that the road ahead bends to the right (or left).

DIAGRAM 46




DOUBLE BEND AHEAD, FIRST TO THE LEFT

This symbol may be reversed to indicate —

DOUBLE BEND AHEAD, FIRST TO THE RIGHT

This sign indicates that there is a double bend of the road ahead.

THE SCHEDULE — continued




SERIES OF BENDS FIRST TO THE RIGHT

This symbol may be reversed to indicate —

SERIES OF BENDS FIRST TO THE LEFT

This sign indicates that there is a series of bends of the road ahead.



SIDE ROAD TO THE RIGHT


This symbol may be reversed to indicate —

SIDE ROAD TO THE LEFT

THE SCHEDULE — continued

This sign indicates that there is a side road junction ahead.

DIAGRAM 49




STAGGERED JUNCTION, LEFT TURN FIRST

This symbol may be reversed to indicate —

STAGGERED JUNCTION, RIGHT TURN FIRST

This sign indicates that there is a staggered junction ahead.


DIAGRAM 50



CROSS ROADS

This sign indicates that there is a cross roads junction ahead.

THE SCHEDULE — continued




MERGING INTO TRAFFIC ON RIGHT

This symbol may be reversed to indicate —

MERGING INTO TRAFFIC ON LEFT

This sign indicates that there a junction ahead where traffic on this road will merge with the traffic on the adjoining road.



TRAFFIC MERGES FROM LEFT


This symbol may be reversed to indicate —

TRAFFIC MERGES FROM RIGHT

This sign indicates that traffic on the adjoining road will merge into traffic on this road.

THE SCHEDULE — continued


DIAGRAM 53



T-JUNCTION

This sign indicates that there is a T-junction ahead.

DIAGRAM 54




DUAL CARRIAGEWAY ENDS AHEAD

This sign indicates that the dual carriageways will merge into a single carriageway ahead.

THE SCHEDULE — *continued*


DIAGRAM 55



ROUNDBOUT AHEAD

This sign indicates that there is a roundabout ahead.

DIAGRAM 56




TRAFFIC SIGNALS AHEAD

This sign indicates that traffic is controlled by traffic light signals ahead.

THE SCHEDULE — *continued*

DIAGRAM 57




PEDESTRIAN CROSSING AHEAD

This sign indicates that there is a pedestrian crossing ahead.

THE SCHEDULE — continued

DIAGRAM 57 (a)




BICYCLE CROSSING AHEAD

This sign indicates that there is a bicycle crossing ahead.

THE SCHEDULE — *continued*

DIAGRAM 57(b)




PEDESTRIAN CROSSING AHEAD MARKING

This marking indicates that there is a zebra crossing ahead and motorists should be prepared to give way to pedestrians crossing the road at the zebra crossing.

[S 257/2009 wef 08/06/2009]

DIAGRAM 57(c)




ADVANCED WARNING LIGHTS

THE SCHEDULE — *continued*

The flashing amber lights indicate to motorists that the traffic light signal ahead is red or going to turn red and motorists should slow down and prepare to stop.

[S 257/2009 wef 08/06/2009]

DIAGRAM 57(d)




INTELLIGENT ROAD STUDS

These intelligent road studs, mounted flush to the road surface, blink when the green man light of the associated pedestrian crossing is illuminated. They indicate to motorists turning right that they should give way to pedestrians crossing the road.

[S 257/2009 wef 08/06/2009]

DIAGRAM 57(e)

THE SCHEDULE — continued



GIVE WAY TO PEDESTRIANS

This sign is placed at a signalised junction, and is usually mounted on top of a traffic light. It indicates for right turning motorists to look out for and to give way to adjacent crossing pedestrians.

[S 158/2018 wef 01/04/2018]

THE SCHEDULE — continued





DIAGRAM 58

CHILDREN

This sign indicates that there is ahead an area where children are likely to be encountered.

DIAGRAM 58(a)




SCHOOL ZONE DRIVE CAREFULLY

THE SCHEDULE — *continued*

This sign is placed at the start of a demarcated school zone. It indicates that the section of the road ahead fronts a school.

[S 782/2013 wef 01/01/2014]

**DIAGRAM 58(b)**




**SCHOOL ZONE DRIVE CAREFULLY**

This sign is placed at the start of a demarcated school zone. It indicates that the section of the road ahead fronts a school.

[S 782/2013 wef 01/01/2014]

THE SCHEDULE — continued


DIAGRAM 59



PEDESTRIAN ON ROAD AHEAD

This sign indicates that there is ahead an area where pedestrian are likely to be encountered.

DIAGRAM 59A




“LOOK” MARKING

This marking is indicated on the road pavement to remind pedestrians to look out for traffic before crossing the road.

[S 158/2018 wef 01/04/2018]

DIAGRAM 59B

THE SCHEDULE — continued




WATCH OUT FOR VEHICLES

This sign informs pedestrians to watch out for oncoming vehicles before crossing the road.

[S 158/2018 wef 01/04/2018]

DIAGRAM 60




STEEP HILL UPWARDS AHEAD

This sign indicates that there is a steep hill upwards ahead.

THE SCHEDULE — continued


DIAGRAM 61



STEEP HILL DOWNWARDS AHEAD

This sign indicates that there is a steep hill downwards ahead.

DIAGRAM 62




SLIPPERY ROAD AHEAD

This sign indicates that the condition of the road surface ahead is dangerous.

THE SCHEDULE — continued


DIAGRAM 63



UNEVEN ROAD

This sign indicates that the road ahead is uneven.


DIAGRAM 64



HEIGHT LIMIT AHEAD


This sign indicates that the section of the road ahead has a height restriction of 4.5m. The numerals on the sign may be altered to indicate different height restriction.

THE SCHEDULE — continued



LEVEL CROSSING WITH GATE OR BARRIER AHEAD

This sign indicates that there is a level crossing with gate or barrier ahead.




LEVEL CROSSING WITHOUT GATE OR BARRIER AHEAD

This sign indicates that there is a level crossing without gate or barrier ahead.

THE SCHEDULE — continued


DIAGRAM 67



HORSES OR PONIES

This sign indicates that there is ahead an area where horses are likely to be encountered.


DIAGRAM 68



ROAD HUMP AHEAD


This sign indicates that there is a road hump ahead.

THE SCHEDULE — continued



NARROW BRIDGE AHEAD

This sign indicates that there is a narrow bridge ahead.




QUAYSIDE OR RIVER BANK AHEAD

This sign indicates that there is a quayside or river bank ahead.

THE SCHEDULE — *continued*

DIAGRAM 71




OTHER DANGER

This sign indicates that there is ahead potential danger which is not covered specifically by any other warning sign.

THE SCHEDULE — *continued*

DIAGRAM 72 (a)




LANE CLOSURE AHEAD  
OFFSIDE LANE CLOSED

This symbol may be reversed to indicate —  
NEARSIDE LANE CLOSED


This sign indicates that there is ahead closure of the lane marked by the red bar.

THE SCHEDULE — continued



CENTRE LANE CLOSURE AHEAD

This sign indicates that there is ahead closure of the centre lane marked by the red bar.




ACCIDENT AREA

This sign indicates the section of the road which is prone to accidents.

THE SCHEDULE — continued

DIAGRAM 74



EXPRESSWAY AHEAD

This sign indicates the approach to an expressway.

DIAGRAM 75

RESTRICTED ZONE AHEAD

[Omitted]

DIAGRAM 76



ELDERLY OR HANDICAPPED PEDESTRIANS

THE SCHEDULE — continued

This sign indicates that there is ahead an area where elderly or handicapped pedestrians are likely to be encountered.



SILVER ZONE, SLOW DOWN

This sign is placed at the start of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road ahead and that motorists should slow down.

DIAGRAM 76B




THE SCHEDULE — *continued*

This sign indicates that motorists must keep a lookout for cyclists.

[S 172/2017 wef 22/04/2017]

[S 670/2014 wef 01/10/2014]

DIAGRAM 77




DIVERSION TO ANOTHER CARRIAGEWAY TO THE RIGHT

This symbol may be reversed to indicate —

DIVERSION TO ANOTHER CARRIAGEWAY TO THE LEFT


This sign indicates that there is a diversion of carriageway ahead.

THE SCHEDULE — continued



DANGER


This sign indicates an obstruction ahead.



MERGE


This sign indicates that there is a merging of traffic ahead.

THE SCHEDULE — continued



U-TURN AHEAD

This sign indicates that vehicles may be making a U-Turn ahead.



U-TURN AHEAD (FROM OPPOSITE DIRECTION)

This sign indicates that vehicles from the opposite direction may be making a U-Turn ahead.

THE SCHEDULE — continued

DIAGRAM 82




LOW FLYING AIRCRAFT

This sign indicates that there is ahead an area where low flying aircraft crossing the path of the road may possibly be encountered.

THE SCHEDULE — *continued*


DIAGRAM 83



TUNNEL AHEAD

This sign indicates that the stretch of road ahead runs through a tunnel.

DIAGRAM 83A




TUNNEL

This sign serves as a supplement to diagram 83 and indicates the presence of a tunnel ahead.

[S 189/2017 wef 28/04/2017]

THE SCHEDULE — continued


DIAGRAM 84



SHARP DEVIATION

This sign indicates that there is a sharp deviation in the road to the left.

DIAGRAM 84A




CURVE ALIGNMENT MARKER

This marking is installed along sharp road bends to indicate to motorists that they are approaching the bends.

[S 158/2018 wef 01/04/2018]

THE SCHEDULE — continued

DIAGRAM 85



BARRIER

This sign indicates a temporary barrier.

PART III

INFORMATIVE SIGNS

DIAGRAM 86 (a)





DIAGRAM 86 (b)




ADVANCE DIRECTIONAL SIGNS

DIAGRAM 86 (c)



DIAGRAM 86 (d)




CONFIRMATORY SIGNS

THE SCHEDULE — continued


Note: In diagrams 86(a) to 86(d), the background of the signs may be in green, blue or white. The symbols and inscriptions on a coloured background are in white or yellow and on a white background, in black.

DIAGRAM 86 (e)



ROCHOR ROAD, KEEP LEFT


DIAGRAM 86 (f)



PUBLIC CAR PARK

THE SCHEDULE — *continued*


DIAGRAM 87



NO THROUGH ROAD

This sign placed at the entry to a road indicates a no through road.

DIAGRAM 88




NO THROUGH ROAD ON SIDE ROAD TO THE RIGHT

This symbol may be reversed to indicate —

NO THROUGH ROAD ON SIDE ROAD TO THE LEFT

This sign indicates that the road on the right (or left) is a no through road.

THE SCHEDULE — continued




ONE WAY STREET

ONE WAY STREET TO LEFT

The arrow may be reversed to point right to indicate —

ONE WAY STREET TO RIGHT

The above indicates that the traffic flow along the road ahead is a one way to the left (or right).




ONE WAY TRAFFIC

This sign indicates the direction of traffic flow on a one way street.

THE SCHEDULE — continued


DIAGRAM 91



U-TURN

This sign indicates that there is ahead a facility where vehicles are permitted to make a U-Turn.


DIAGRAM 92



U-TURNING VEHICLES KEEP RIGHT


THE SCHEDULE — continued

DIAGRAM 93



DUAL CARRIAGEWAY AHEAD


DIAGRAM 94



SLOW


THE SCHEDULE — continued

DIAGRAM 95



REDUCE SPEED NOW

DIAGRAM 95A



‘YOUR SPEED’ SIGN


The electronic sign will flash a motorist’s real time speed, thereby indicating to the motorist whether he should slow down to obey the speed limit.

[S 257/2009 wef 08/06/2009]




THE SCHEDULE — continued

DIAGRAM 98



END OF RESTRICTED ZONE

DIAGRAM 99




START OF EXPRESSWAY





THE SCHEDULE — *continued*

DIAGRAM 104



END OF EXPRESSWAY

This sign indicates the end of an expressway.

THE SCHEDULE — continued

DIAGRAM 105





DIAGRAM 106



EXPRESSWAY KILOMETRE SIGN


Diagram 107(a)

[Deleted by S 538/2011 wef 21/09/2011]



THE SCHEDULE — *continued*

DIAGRAM 107(d)



TAXI STOP

This sign indicates the specified number of taxis that may use the taxi stop at any one time.

[S 165/2011 wef 29/03/2011]

Diagram 108


[Deleted by S 538/2011 wef 21/09/2011]

Diagram 108A

[Deleted by S 538/2011 wef 21/09/2011]

THE SCHEDULE — *continued*

DIAGRAM 108B




TAXI STAND

This sign indicates the location of a taxi stand.

[S 165/2011 wef 29/03/2011]

THE SCHEDULE — *continued*

DIAGRAM 108C




TAXI STAND

This sign indicates the specified number of taxis that may use the taxi stand at any one time.

[S 165/2011 wef 29/03/2011]

DIAGRAM 109




PASSENGER PICK-UP POINT

THE SCHEDULE — continued

Diagram 110

[Deleted by S 538/2011 wef 21/09/2011]

DIAGRAM 110A



TAXI DROP-OFF POINT

This sign indicates the location of a taxi drop-off point.

[S 375/2001 wef 03/08/2001]

Diagram 111

[Deleted by S 538/2011 wef 21/09/2011]





THE SCHEDULE — *continued*

DIAGRAM 114



PART-DAY BUS LANE

[S 134/2007 wef 01/04/2007]

THE SCHEDULE — continued

DIAGRAM 114A




FULL-DAY BUS LANE

[S 114/2016 wef 21/03/2016]

[S 134/2007 wef 01/04/2007]

DIAGRAM 115 (a)



THE SCHEDULE — *continued*

AT SIGNALISED INTERSECTION FOR PART-DAY BUS LANE

[S 639/2005 wef 03/10/2005]

DIAGRAM 115 (b)




DIAGRAM 115 (c)





DIAGRAM 115 (d)




AT UNCONTROLLED JUNCTIONS  
OR OPENINGS

PART-DAY BUS LANE MARKINGS

[S 639/2005 wef 03/10/2005]

DIAGRAM 115 (e)




THE SCHEDULE — *continued*

AT SIGNALISED INTERSECTION FOR FULL-DAY BUS LANE


[S 639/2005 *wef* 03/10/2005]

DIAGRAM 115 (f)




[S 639/2005 *wef* 03/10/2005]

DIAGRAM 115 (g)



[S 639/2005 *wef* 03/10/2005]

DIAGRAM 115 (h)




THE SCHEDULE — *continued*

AT UNCONTROLLED JUNCTIONS OR OPENINGS

FULL-DAY BUS LANE MARKINGS

[S 639/2005 wef 03/10/2005]


DIAGRAM 116 (a)



BUS STOP

This sign indicates the location of bus stop.

DIAGRAM 116(aa)




BUS STOP

THE SCHEDULE — continued

This sign indicates the location of a bus stop.


[S 375/2001 wef 03/08/2001]

DIAGRAM 116 (b)



This sign indicates the location of bus terminus.

DIAGRAM 116 (c)




BUS ZONE

The markings indicate a bus zone box reserved for an omnibus to pick up or set down passengers.

THE SCHEDULE — *continued*


DIAGRAM 116(d)



MARKINGS FOR A BUS GIVE-WAY CONTROLLED AREA, BUS GIVE-WAY LINE AND BUS GIVE-WAY BOX

[S 651/2008 wef 20/12/2008]

DIAGRAM 117




RAIN SHELTER

This sign indicates the location of rain shelter.


THE SCHEDULE — continued

DIAGRAM 118




CONCEALED EXIT AHEAD

DIAGRAM 119



EXCEPT SCHOOL BUSES

DIAGRAM 120




EXCEEDING 2,500 KG IN UNLADEN WEIGHT




THE SCHEDULE — continued

DIAGRAM 124



VEHICLES NOT EXCEEDING 2,500 KG IN UNLADEN WEIGHT

DIAGRAM 125 (a)




PEDESTRIAN CROSSING

This sign indicates the location of a pedestrian crossing.

THE SCHEDULE — *continued*


DIAGRAM 126



DIRECTION OF TEMPORARY PEDESTRIAN ROUTE

This sign indicates that there is a temporary footway for pedestrian to the left. The arrow may be reversed or a double headed arrow may be used to indicate a temporary footway for pedestrian to the right or to the left and right respectively.

DIAGRAM 127




UNDERPASS

This sign indicates the location of a pedestrian underpass.

THE SCHEDULE — *continued*


DIAGRAM 128



OVERPASS

This sign indicates the location of a pedestrian overpass.

DIAGRAM 129 (a)




RED MAN

GREEN MAN

LIGHT SIGNALS FOR PEDESTRIANS


THE SCHEDULE — continued

DIAGRAM 129 (b)



GREEN LIGHT SIGNAL FOR OMNIBUSES

DIAGRAM 129 (c)




BICYCLE CROSSING

This sign indicates the location of a bicycle crossing.

THE SCHEDULE — *continued*

DIAGRAM 129(ca)




BICYCLE CROSSING SIGN

This sign indicates the location of a bicycle crossing.

[S 276/2018 wef 05/05/2018]

THE SCHEDULE — *continued*

DIAGRAM 129 (d)




DIRECTION OF TEMPORARY CYCLIST ROUTE


This sign indicates that there is a temporary pathway for cyclist to the left. The arrow may be reversed or a double headed arrow may be used to indicate a temporary footway for cyclist to the right or to the left and right respectively.

THE SCHEDULE — *continued*

DIAGRAM 129 (e)



RED BICYCLE




GREEN BICYCLE

LIGHT SIGNALS FOR BICYCLES

THE SCHEDULE — *continued*


DIAGRAM 130



SCALE: 1:20

THE SCHEDULE — continued


DIAGRAM 131



SCALE: 1:20

THE SCHEDULE — *continued*


DIAGRAM 132



SPEED REGULATING STRIPS AHEAD


THE SCHEDULE — *continued*

DIAGRAM 133




THE SCHEDULE — *continued*

DIAGRAM 134



THE SCHEDULE — *continued*


DIAGRAM 135



MARKINGS FOR A ROAD HUMP

THE SCHEDULE — continued

DIAGRAM 135A





TRAFFIC CALMING MARKINGS

These markings consist of 2 rows of white triangles which are intended to create a visually narrowed lane to slow down the speed of motorists.

[S 257/2009 wef 08/06/2009]

THE SCHEDULE — continued


DIAGRAM 136



START OF TUNNEL

THE SCHEDULE — *continued*


DIAGRAM 137



LANE INDICATION ARROWS (WITH TIME RESTRICTIONS)

THE SCHEDULE — *continued*

DIAGRAM 138 (a)




MERGE ARROWS

This marking indicates that the 2 lanes with the marking will merge into a single lane ahead.



THE SCHEDULE — *continued*


This marking indicates that vehicles on the lane with the marking may only proceed ahead, turn left or right.



EDGE OF ROAD MARKINGS

THE SCHEDULE — *continued*

DIAGRAM 140 (a)




MARKINGS AT SIGNAL-CONTROLLED JUNCTION

[S 572/2005 wef 01/09/2005]


THE SCHEDULE — *continued*

DIAGRAM 140 (b)



YELLOW BOX AT JUNCTION


DIAGRAM 140 (c)



YELLOW BOX NEAR BUS BAY

THE SCHEDULE — *continued*


DIAGRAM 140 (d)



YELLOW BOX AT EXIT OF SLIP ROAD

THE SCHEDULE — *continued*

DIAGRAM 140 (e)




MARKINGS AT SIGNAL-CONTROLLED JUNCTION

[S 572/2005 wef 01/09/2005]


THE SCHEDULE — *continued*

DIAGRAM 140 (f)




YELLOW BOX NEAR 'U' TURN OPENING

DIAGRAM 140 (g)



YELLOW BOX NEAR DEMARCATED BUS BAY


DIAGRAM 140 (h)



YELLOW BOX NEAR DRIVEWAY


THE SCHEDULE — continued

DIAGRAM 140 (i)



YELLOW BOX NEAR BAY

DIAGRAM 141




RIGHT TURN POCKET

This marking is intended to guide motorists making a right turning at a junction as to the path they should take.

THE SCHEDULE — *continued*


DIAGRAM 142 (a)






THE SCHEDULE — *continued*

DIAGRAM 143 (a)




THE SCHEDULE — *continued*

DIAGRAM 143 (b)




THE SCHEDULE — *continued*

DIAGRAM 144 (a)




THE SCHEDULE — *continued*

DIAGRAM 144 (b)



THE SCHEDULE — *continued*


DIAGRAM 145



SIGNALISED PEDESTRIAN CROSSING

[S 572/2005 wef 01/09/2005]

DIAGRAM 145(a)




SIGNALISED BICYCLE CROSSING

[S 276/2018 wef 05/05/2018]

THE SCHEDULE — continued


DIAGRAM 146

U-TURN MARKINGS



TYPICAL U-TURN MARKINGS ON A DUAL-CARRIAGEWAY


SCALE: 1:1000



U-TURN MARKINGS

THE SCHEDULE — *continued*


DIAGRAM 147



DOUBLE LINES AND HATCHED MARKINGS ON SHARP BENDS

THE SCHEDULE — continued

DIAGRAM 147A




BROADER ALIGNMENT LANE MARKINGS (BALM)

These markings are found along bends on expressways and major arterial roads. The markings guide motorists to be better aligned to their lanes.

[S 158/2018 wef 01/04/2018]


DIAGRAM 148 (a)



DIVERGING TRAFFIC


THE SCHEDULE — continued

DIAGRAM 148 (b)




MERGING TRAFFIC

DIAGRAM 148 (c)



TWO WAY TRAFFIC CHEVRON MARKINGS

DIAGRAM 149 (a)




ACCELERATION LANE

SINGLE ENTRY

THE SCHEDULE — *continued*


DIAGRAM 149 (b)



DECELARATION LANE

SINGLE ENTRY

DIAGRAM 149 (c)



CHEVRON MARKINGS FOR EXPRESSWAY

THE SCHEDULE — continued

DIAGRAM 149 (d)






DIAGRAM 149 (e)



THE SCHEDULE — *continued*

DIAGRAM 149 (f)




**INCLINED BROKEN YELLOW LINE**

The line is used to guide drivers emerging from the side road to keep away from the leftmost traffic lane which is a bus lane. It gives the road user advance warning and provides clearer guidance to motorists of bus lane ahead.

DIAGRAM 150 (a)

**LONGITUDINAL MARKINGS**


**CENTRE / LANE LINES**



**DOUBLE WHITE LINES AT THE CENTRE OF A TWO WAY ROAD  
OR BETWEEN LANES**


THE SCHEDULE — *continued*

DIAGRAM 150 (b)




SINGLE WHITE LINE AT THE CENTRE OF A TWO WAY ROAD

DIAGRAM 150 (c)



BROKEN WHITE LINES AT THE CENTRE OF A TWO WAY ROAD


DIAGRAM 150 (d)



BROKEN WHITE LINES BETWEEN LANES


THE SCHEDULE — continued

DIAGRAM 151 (a)



BROKEN WHITE LINES BETWEEN LANES  
INDICATING THE APPROACH TO A STOP LINE AT A JUNCTION


DIAGRAM 151 (b)



BROKEN WHITE LINES INDICATING THE EDGE OF  
THE MAIN ROAD AT —

- (i) Bus Bay and Lay-Bys
- (ii) Slip road, including acceleration and deceleration lanes
- (iii) Exclusive right turn lanes


DIAGRAM 151 (c)



BROKEN WHITE LINES INDICATING THE EDGE OF  
UNDIVIDED STRAIGHT ROAD


THE SCHEDULE — *continued*

DIAGRAM 151 (d)




SINGLE WHITE LINE INDICATING THE EDGE OF A ROAD WHERE THERE IS IMMINENT HAZARD

DIAGRAM 151 (e)



SINGLE WHITE LINE DEMARCATING THE HARD SHOULDER SECTION ON AN EXPRESSWAY


DIAGRAM 151 (f)



An edgeline is a continuous white line of a width of 200 mm painted alongside the edge of a carriageway or alongside the central dividing kerb of a dual carriageway. It is a supplementary guiding line to be provided on selected roads wherever necessary.

DIAGRAM 152 (a)


PARKING RESTRICTION LINES



Single yellow line at the edge of a road prohibiting parking from 7am to 7pm on any day except Sundays or gazetted public holidays.


THE SCHEDULE — continued

DIAGRAM 152 (b)



Double yellow lines at the edge of a road prohibiting parking at all times.


DIAGRAM 152 (c)



Single zig zag yellow line at the edge of a road prohibiting parking at all times.


THE SCHEDULE — continued

DIAGRAM 152 (d)



Double zig zag yellow lines at the edge of a road prohibiting stopping of vehicles at all times unless the vehicle is prevented from proceeding due to traffic conditions.

DIAGRAM 152(e)



The red transverse lines of not less than 1,000 mm in width are laid down perpendicular to the edge of a road. These lines indicate that the parking of any vehicle is prohibited along the length of the road starting from the point where those lines are indicated, to the point the lines end.

[S 172/2017 wef 22/04/2017]

TRANSVERSE MARKINGS

THE SCHEDULE — continued

A STOP LINE


DIAGRAM 153



Single white line indicating position on a road where vehicles are required to stop in compliance with a 'STOP' sign, traffic signal or the direction of police officers.

B GIVE WAY LINE


DIAGRAM 154



Broken double white lines indicating the position on a road where vehicles are required to give way to traffic on the right or left, as the case may be, in compliance with a 'GIVE WAY' sign.

C GIVE WAY TRIANGULAR MARKING


DIAGRAM 155



Marking indicating that vehicles are required to give way to traffic on the right or left, as the case may be.

THE SCHEDULE — *continued*


DIAGRAM 156



TYPICAL ARRANGEMENT OF PARKING LOTS

THE SCHEDULE — *continued*

DIAGRAM 157




This sign indicates that the parking lot is reserved for a vehicle driven by a disabled person.

[Diagrams 158 and 159 deleted by S 461/98]


THE SCHEDULE — continued

DIAGRAM 160 (a)



THE SCHEDULE — continued


DIAGRAM 160 (b)





THE SCHEDULE — continued


DIAGRAM 160 (d)



THE SCHEDULE — *continued*


— continued

DIAGRAM 160 (e)




THE SCHEDULE — continued

DIAGRAM 160 (f)



THE SCHEDULE — *continued*


DIAGRAM 161 (a)





THE SCHEDULE — *continued*

DIAGRAM 161 (c)



THE SCHEDULE — continued

DIAGRAM 161 (d)






DIAGRAM 161 (e)





THE SCHEDULE — continued

DIAGRAM 161 (g)



[S 3/2005 wef 03/01/2005]

THE SCHEDULE — continued

DIAGRAM 162





DIAGRAM 163



JUMPING AMBER LIGHTS


The jumping amber lights will flash alternately between the words “SCH” and “ZONE” to indicate to motorists that they are approaching a school zone and

THE SCHEDULE — *continued*

they should slow down and drive carefully with regard to school children crossing the roads.

[S 83/2000 wef 01/03/2000]

DIAGRAM 164




END OF SCHOOL ZONE

This sign is placed at the end of a demarcated school zone. It indicates that the section of the road before fronts a school.

[S 782/2013 wef 01/01/2014]

THE SCHEDULE — *continued*


DIAGRAM 165



END OF SILVER ZONE

This sign is placed at the end of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road before.


DIAGRAM 166



Markings indicating a bicycle lane.


DIAGRAM 167(a)

THE SCHEDULE — *continued*



A bicycle lane at a signalised intersection.

DIAGRAM 167(b)



A bicycle lane at a bus stop.

BICYCLE LANES AT UNCONTROLLED JUNCTIONS OR OPENINGS

DIAGRAM 168(a)

THE SCHEDULE — *continued*




DIAGRAM 168(b)




DIAGRAM 168(c)




DIAGRAM 169

THE SCHEDULE — *continued*



This sign indicates that cyclists are likely to be encountered in the section of road ahead, and that motorists should slow down.

DIAGRAM 170(a)



THE SCHEDULE — *continued*

This sign indicates the start of a bicycle lane.

DIAGRAM 170(b)



This sign indicates the end of a bicycle lane.

[S 172/2017 wef 22/04/2017]

[S 670/2014 wef 01/10/2014]

[S 276/2018 wef 05/05/2018]

[G.N. Nos. S 501/91; S 442/92; S 540/93; S 341/94;  
S 466/94; S 48/95; S 61/95; S 192/95; S 205/95; S 229/95;  
S 538/95; S 171/96; S 319/96; S 196/97; S 223/97;  
S 482/97; S 179/98; S 461/98; S 636/98; S 191/99]

LEGISLATIVE HISTORY  
ROAD TRAFFIC (TRAFFIC SIGNS) RULES  
(CHAPTER 276, R 33)

This Legislative History is provided for the convenience of users of the Road Traffic (Traffic Signs) Rules. It is not part of these Rules.

**1. G. N. No. S 501/1991 — Road Traffic (Traffic Signs) Rules 1991**

Date of commencement : 15 November 1991

**2. 1990 Revised Edition — Road Traffic (Traffic Signs) Rules**

Date of operation : 25 March 1992

**3. G. N. No. S 442/1992 — Road Traffic (Traffic Signs) (Amendment) Rules 1992**

Date of commencement : 23 October 1992

**4. G. N. No. S 540/1993 — Road Traffic (Traffic Signs) (Amendment) Rules 1993**

Date of commencement : 3 January 1994

**5. G. N. No. S 341/1994 — Road Traffic (Traffic Signs) (Amendment) Rules 1994**

Date of commencement : 9 September 1994

**6. G. N. No. S 466/1994 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 1994**

Date of commencement : 15 December 1994

**7. G. N. No. S 48/1995 — Road Traffic (Traffic Signs) (Amendment) Rules 1995**

Date of commencement : 11 February 1995

**8. G. N. No. S 61/1995 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 1995**

Date of commencement : 18 February 1995

**9. G. N. No. S 192/1995 — Road Traffic (Traffic Signs) (Amendment No. 3) Rules 1995**

Date of commencement : 24 April 1995

**10. G. N. No. S 205/1995 — Road Traffic (Traffic Signs) (Amendment No. 4) Rules 1995**

Date of commencement : 2 May 1995

**11. G. N. No. S 229/1995 — Road Traffic (Traffic Signs) (Amendment No. 5)  
Rules 1995**

Date of commencement : 1 June 1995

**12. G. N. No. S 538/1995 — Road Traffic (Traffic Signs) (Amendment No. 6)  
Rules 1995**

Date of commencement : 1 December 1995

**13. G. N. No. S 171/1996 — Road Traffic (Traffic Signs) (Amendment)  
Rules 1996**

Date of commencement : 19 April 1996

**14. G. N. No. S 319/1996 — Road Traffic (Traffic Signs) (Amendment No. 2)  
Rules 1996**

Date of commencement : 19 July 1996

**15. G. N. No. S 196/1997 — Road Traffic (Traffic Signs) (Amendment)  
Rules 1997**

Date of commencement : 16 April 1997

**16. G. N. No. S 223/1997 — Road Traffic (Traffic Signs) (Amendment No. 2)  
Rules 1997**

Date of commencement : 5 May 1997

**17. G. N. No. S 482/1997 — Road Traffic (Traffic Signs) (Amendment No. 3)  
Rules 1997**

Date of commencement : 31 October 1997

**18. G. N. No. S 179/1998 — Road Traffic (Traffic Signs) (Amendment)  
Rules 1998**

Date of commencement : 1 April 1998

**19. G. N. No. S 461/1998 — Road Traffic (Traffic Signs) (Amendment No. 2)  
Rules 1998**

Date of commencement : 1 September 1998

**20. G. N. No. S 636/1998 — Road Traffic (Traffic Signs) (Amendment No. 3)  
Rules 1998**

Date of commencement : 1 January 1999

**21. G. N. No. S 191/1999 — Road Traffic (Traffic Signs) (Amendment)  
Rules 1999**

Date of commencement : 14 April 1999

- 22. 1999 Revised Edition — Road Traffic (Traffic Signs) Rules**  
Date of operation : 30 September 1999
- 23. G. N. No. S 13/2000 — Road Traffic (Traffic Signs) (Amendment) Rules 2000**  
Date of commencement : 14 January 2000
- 24. G. N. No. S 83/2000 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2000**  
Date of commencement : 1 March 2000
- 25. G. N. No. S 375/2001 — Road Traffic (Traffic Signs) (Amendment) Rules 2001**  
Date of commencement : 3 August 2001
- 26. G. N. No. S 549/2001 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2001**  
Date of commencement : 1 November 2001
- 27. G. N. No. S 334/2003 — Road Traffic (Traffic Signs) (Amendment) Rules 2003**  
Date of commencement : 14 July 2003
- 28. G. N. No. S 3/2005 — Road Traffic (Traffic Signs) (Amendment) Rules 2005**  
Date of commencement : 3 January 2005
- 29. G. N. No. S 572/2005 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2005**  
Date of commencement : 1 September 2005
- 30. G. N. No. S 577/2005 — Road Traffic (Traffic Signs) (Amendment No. 3) Rules 2005**  
Date of commencement : 5 September 2005
- 31. G. N. No. S 639/2005 — Road Traffic (Traffic Signs) (Amendment No. 4) Rules 2005**  
Date of commencement : 3 October 2005
- 32. G. N. No. S 134/2007 — Road Traffic (Traffic Signs) (Amendment) Rules 2007**  
Date of commencement : 1 April 2007

**33. G. N. No. S 651/2008 — Road Traffic (Traffic Signs) (Amendment) Rules 2008**

Date of commencement : 20 December 2008

**34. G. N. No. S 257/2009 — Road Traffic (Traffic Signs) (Amendment) Rules 2009**

Date of commencement : 8 June 2009

**35. G. N. No. S 165/2011 — Road Traffic (Traffic Signs) (Amendment) Rules 2011**

Date of commencement : 29 March 2011

**36. G. N. No. S 538/2011 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2011**

Date of commencement : 21 September 2011

**37. G. N. No. S 814/2013 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2013**

Date of commencement : 29 December 2013

**38. G. N. No. S 782/2013 — Road Traffic (Traffic Signs) (Amendment) Rules 2013**

Date of commencement : 1 January 2014

**39. G. N. No. S 670/2014 — Road Traffic (Traffic Signs) (Amendment) Rules 2014**

Date of commencement : 1 October 2014

**40. G.N. No. S 114/2016 — Road Traffic (Traffic Signs) (Amendment) Rules 2016**

Date of commencement : 21 March 2016

**41. G.N. No. S 676/2016 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2016**

Date of commencement : 1 January 2017

**42. G.N. No. S 172/2017 — Road Traffic (Traffic Signs) (Amendment) Rules 2017**

Date of commencement : 22 April 2017

**43. G.N. No. S 189/2017 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2017**

Date of commencement : 28 April 2017

**44. G.N. No. S 158/2018 — Road Traffic (Traffic Signs) (Amendment)  
Rules 2018**

Date of commencement : 1 April 2018

**45. G.N. No. S 276/2018 — Road Traffic (Traffic Signs) (Amendment No. 2)  
Rules 2018**

Date of commencement : 5 May 2018

**46. G.N. No. S 95/2020 — Road Traffic (Traffic Signs) (Amendment)  
Rules 2020**

Date of commencement : 1 March 2020